



THE CORPORATION OF THE **TOWN OF COBALT**

Fire Hall Foundation Repair & Backup Generator Pad Installation

Requirement for the repair of South wall foundation & to Install a concrete backup generator pad

South wall is leaking into basement requires excavation along foundation and sealing c/w new drainage consideration.

Design and build concrete generator pad to accommodate backup generator, size of pad to be determined on site approx... size 3.6m L x 3.6m W x 0.450m D c/w spill containment provision.

Landscape the area with 75mm of 19mm washed crushed limestone stone

Installation of electrical cabling to accommodate from generator to inside gang box. Approx... run is 20 meters.